Sl. No.	Description of Items
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal thro upto 2 metrs and an average lift upto 0.5 m, excavated surface leveled d sides neat dresses the disposed earth to be levelled neatley after breaking of clods complete as p specifications.
2	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manual (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cable and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5r excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking clods and neatly dressed as per specifications,
3	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1: including fixing curing etc., complete as per specifications.
4	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bour macadam specification including spreading in uniform thickness, hand packing, rolling with wheeled steel/vibratory roller 8-10 tonnes in stages to proper grade and camber, applying ar brooming requisite type of screening/binding Materials to fill up the interstices of coars aggregate, watering and compacting to the required density Complete as per Specification. By Mechanical means. MORTH Specification No.404 Type A 13.2mm for grading II
5	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bour macadam specification including spreading in uniform thickness, hand packing, rolling with wheeled steel/vibratory roller 8-10 tonnes in stages to proper grade and camber, applying ar brooming requisite type of screening/binding Materials to fill up the interstices of coars aggregate, watering and compacting to the required density Complete as per Specification. By Mechanical means. MORTH Specification No. Specification No.404Type B 11.2mm fo grading III
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by th engineer in charge of the work, lead 15 Km a) Basic rate for haulage of materilas as per iter No. 17.4/KSRRB : M 100-4.1 .... Rs. 2.00 Tonne/ Km b) Average earth of work 1.28 Tonne/Ki for Rs. 2.00/Km c) Add loading and unloading

1 CERTIFICATE

2 This is to certify that the contractor has completed the work satisfactorily.

3 The contractor has cleared the debries from the work sport

4 The contractor has used his own vehicles for the coveying the debries.

There are no departmental issues for the above work.

Ravi. N.K.

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಶೆಟಿಹಳ್ಳಿ ಉಪವಿಭಾಗ, ದಾಸರಹಳ್ಳಿ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ಎಸ್.ಎಂ ರಸ್ತೆ, ರವೀಂದ್ರನಗರ, ಬೆಂಗಳೂರು